



Truettown

Acid Mine Treatment Plant
and Pigment Production

May 05 - 06, 2026

Agenda



Project Overview

AECOM

Design Basis


AECOM


Project Status



Social & Environmental Impact

Q&A






Partnering for Success

- Ohio Department of Natural Resources
- U.S. Department of the Interior – Office of Surface Mining
- Rural Action/True Pigments
- Ohio University
- AECOM







Overview


- Partnerships
- Past projects and research
- Background on the Truetown discharge and UGM Complex
- Truetown's impact on Sunday Creek





Abandoned Coal Mines of Ohio





Partnership Spotlight – ODNR and Sunday Creek Watershed Group


- Beginning in 1999 with the formation of the Sunday Creek Watershed Group
- 2002 First Watershed Coordinator
- 2004 First AMD Project – Congo Run Stream Capture
- 2013 Pine Run Doser
- Education and outreach
- Operation and maintenance
- Water and biological sampling
- Truetown and True Pigments



One of Rodger's Hollow primary stream captures during wet conditions, Photo by Sunday Creek Watershed Group



Completed natural channel stream Photo by Kaabe Shaw



Education and Outreach

- Over 100 people have toured the Truetown site each year since Rural Action purchased property
- Ohio University and Hocking College classes are frequent visitors
- Coal India delegation visited in October 2024
- Groundbreaking brought 90+ folks to the site for celebration





Past Projects and Research



- Electrolysis
- Dr. Reifler's initial treatment approach
- Pilot plant
- OU research – Dr. Reifler (OU Engineering) and John Sabraw (OU Prof. Fine Arts)
- Rural action
- Visit PA treatment sites
- Aveka – spray drying
- WesTech – settling and filter testing
- AECOM – design
- Filter press purchase
- Solar drying (OU)
- Site development









Visiting AMD Treatment Sites in PA






Site Development






Site Development






Site Development





Truetown Discharge

- 1983, a seal at a pumping station failed draining water from the Truetown mine severely impacts lower 7 miles of Sunday Creek which runs through the Village of Chauncey
- Flow = 2.2 cfs = 996 gpm = 1.43 MGD
- Fe = 252 mg/L, Al = 2.1 mg/L, Mn = 5 mg/L
- pH = 5.3, Acidity = 430 mg CaCO₃/L, Alkalinity = 22 mg CaCO₃/L
- CO₂ (aq) = 235 mg/L
- TDS = 2,300 mg/L, conductivity = 2,200 μSi/cm
- SO₄²⁻ = 1,511 mg/L, Cl⁻ = 20.6 mg/L, Na⁺ = 190 mg/L, Ca²⁺ = 178 mg/L, Mg²⁺ = 56 mg/L



Hydrogeologic Characterization

- Sarah Kreitzer – Hydrologist
- Omar Beckford – Hydrologist
- Steve Ball – Hydrologist
- Tom Mastrorocco – Geographer



Hydrogeologic Characterization of the Truetown Mine Pool (Ohio)

Technical Assistance Report

Technical Support Division, Water, Geological & Geospatial Branch (WGGB)
Office of Surface Mining Reclamation and Enforcement (OSMRE)


Presented by: Sarah Kreitzer, Hydrologist

Date: July 30, 2024



Office of Surface Mining Reclamation & Enforcement | [OSMRE.GOV](https://www.osmre.gov)





Truetown Mine Complex Overview

Location: Southeastern Ohio, Athens County


Mining History: The Truetown mine complex consists of approximately 14 room-and-pillar mines in the Middle Kittanning (No. 6) coal seam in Athens County, Ohio; mining ceased in 1993

Current State: 75% flooded, acid generation in unflooded areas

Mine Footprint: 14,240 acres

Truetown Discharge: Largest AMD discharge in Ohio (avg. 1,004 gpm) located in Sunday Creek watershed






Main Pool Characteristics

Flooded Extent: ~75% of the mine complex



Shoreline Elevation: ~668 feet AMSL (same as Truetown discharge)


Recharge: Primarily vertical infiltration, some from adjacent mines and groundwater

Estimated Recharge Rate: 0.07 gpm/acre




Mapping by Tom Mastrococco






Monitoring Wells and Discharges

Kottyan WQ
pH – 7.4
Net alk. – 186 mg/L
Total Fe – 2.02 mg/L








Beam Bore Hole Routed to the Wetland



Truetown's Impact

Sunday Creek Watershed






Ohio AMD Program (ODNR DMRM) Watershed Restoration Goals for Impacted Watersheds




Category	Parameter	Watershed and/or Stream Reach Goal
Chemical	pH ¹	6.5 - 9.0 (s.u.)
	Total Iron ¹	< 1.0 (mg/l)
	Total Aluminum ²	Watershed and/or site specific (0.75 mg/L)
	Alkalinity	Net alkaline conditions
Physical Habitat	QHEI ³	≥ 60
Biological	IBI ³	Meets WWH ALUD (44)
	MAIS ⁴	≥ 12

¹Ohio EPA Water Quality Standards Program, Numeric Chemical Criteria
²U.S. EPA Aquatic Life Criteria for Aluminum in Freshwater
³Ohio EPA Biological Criteria for the Protection of Aquatic Life
⁴Studies (Kinney, 2006 and Johnson 2009) using MAIS for Assessing AMD Impacts on Streams


Source: Table from Rush Creek AMDAT Part 2. 2025



Truetown Discharge Meets Sunday Creek



Truetown discharge meets Sunday Creek 24




SCMS073 – Upstream Discharge



Biology and Chemistry Snapshot

- MAIS 15
- IBI – 40
- Net Alkaline – 78.0 mg/L
- Total Fe – 0.81 mg/l
- Total Al – 0.05 mg/L
- QHEI – 70



SCMS0732 – Downstream Discharge

Biology and Chemistry Snapshot

- MAIS 10
- IBI – 14
- Net Acid – 91 mg/L
- Total Fe – 90 mg/L
- Total Al – 1 mg/L





02

Design Basis



Initial Design Basis




Water Side Design Basis

- 600-1500 gpm per train (2x)
- Mechanical redundancies due to lack of mine storage
 - Parallel treatment trains – pigment train can be operated as standard water treatment train
 - Ability to run in parallel as AMD Treatment
 - Emergency treatment train with settling pond

Pigment Production & Processing

- 600-1000 gpm running in series w/ Water Treatment Train
- Pigment train will be backup water treatment train (no pigment production)
- Filter, dewater, grind, dry and package solids
 - 8,965 lbs/day of pH adjusted solids

Initial Target Project Cost: \$10M



Truetown AMD Treatment




Known Treatment Chemistry


- AMD treatment is known
 - Remove excess CO_2
 - Treat with hydrated lime ($\text{Ca}(\text{OH})_2$)
 - Raise pH to 8.0
 - Precipitate solids (Fe, Al, Mg)
 - Settle solids and pump back to mine
 - Use wetlands to provide polishing and buffer before re-entering Sunday Creek


AMD Treatment Challenges

- Minimal treatment buffer since mine is not being pumped down
 - Concern about altering the mine water chemistry
- Change location of seep closer to facility to minimize scaling issues
 - Testing to make sure water chemistry is the same
 - Upcoming tests to make sure flow is connected and original seep will stop flowing





Simplified Process Flow – Pigment Production





Simplified Process Flow – AMD (2x 100%)





Project Approach – IRRT



Pigment Production

- IRRT flow: 600-1000 gpm
 - Excess flow will be diverted to regular treatment side
- Selectively precipitate Fe
- Concentrate, dewater, dry and package iron sludge
- Pigment criteria:
 - Purity > 90% Fe by weight
 - >95% dry by weight
 - Size = less than 30 micron

Additional Testing Needed for IRRT

- Previous testing done by OU in batch
 - Addition of H_2O_2 while maintaining pH at ~4 with caustic
- Mixed results on dewatering tests
- Lack of kinetic data needed for scale up



Project Approach – Parallel Design Paths



Main Treatment Design Parallel to IRRT Testing

- IRRT sludge processing to be in separate building/warehouse
 - Small part of overall site development and water treatment plan
 - IRRT design independent of MDTP
 - Merge designs into single overall design at 60-70%

Challenges in IRRT Design

- Oxidation methods explored
 - H_2O_2 , O_3 , and Ferrate (Fe^{+6})
- New approach to making pigment quality solids discovered
 - Oxidizing without adjusting pH
 - Higher quality solids that are easier to filter
 - Better pigment quality
- Downside – only removes 50% of the iron in the pigment step; with pH adjustment, yield was ~99%

Pigment Recovery and Processing – Tale of Two Solids




Original (pH adjusted solids)

- Polymer selection known
- 99% yield
- Solids settle faster
- Difficult to dewater:
 - Increased filter areas needed
 - High water content in solids make drying expensive
- Less marketable color

Low-pH Solids

- Need to evaluate polymers for settling
- 50% yield
- Finer solids – slower settling rate
 - Increased clarifier size
- Improved filtration – faster filtering with thicker cake
- Color more consistent with commercial colors

Solids selection impacts equipment specifications



Pigment Recovery and Processing – Tale of Two Solids



Additional Testing and Evaluations

- Additional settling tests needed
- Challenges in filtration, drying and packaging
 - Filter options: plate & frame; rotary drum; tube press
 - Drying options: spray drier; rotary vacuum dryer; all electric – no gas available
 - Packaging challenges: dust control; moisture control (95% dry spec)


Path Forward – April 2025

- Added uncertainty in IRRT solids handling approach causing project delays
- IRRT pigment processing removed from scope
 - IRRT process train still in scope
 - Need larger pilot or full-scale information to design drying/packaging equipment
 - Decided that future IRRT would be a standalone project
- Maintain pilot/research area in main control building to gather information on IRRT sludge




03

Project Status





Project Status – No IRRT Processing


- IRRT treatment train still exists
 - Settling test were very dependent on polymer dosage but polymer impacts pigment quality
 - Due to the IRRT being in series, solids carryover is less critical
 - Low-pH solids are the preferred product for pigment
 - Caustic system was removed – only lime for pH adjustment
- Pigment testing to continue once facility is in service
 - Batch tank testing area in operations building
 - Ability to treat raw water or process sludge from clarifier
 - Plan to purchase small filter to develop design information on large scale pigment production
 - Once design information is better defined, expected to be a separate future project




Current Design Concept













Challenge #2 – Too Expensive

	Price
Original ODNR target	\$10M
Initial ROM at start of design	\$25-30M
Estimated TIC based on 'wanted' design @ 65%	\$54M
Key Drivers of Cost	
Destination wetlands with walkways, sculptures and scenic overlook	\$6.5M
Fire protection	\$2.8M
Buildings and facilities	\$14.8M
Value Engineering Effort	
Reduce building footprint Simplify wetlands Reduce inlet pump (from 4 to 2) Remove fire water tank and sprinkler requirements by adjusting H ₂ O ₂ location and using a dry-hydrant design that pulls from new firewater pond	
Estimated Cost After Value Engineering	\$39M

Preliminary Wetlands Design





Path Forward – Phase 1




Finish design on water treatment trains, facility civils, sludge management and chemical delivery systems

Phase 1



Complete the simplified wetland design



Complete the operations building design

Looking for supplemental funding opportunities to offset construction costs



- Two – raw water influent pumps
- Alkaline addition
- Emergency basin
- Sludge pump back
- Wetland




04

**Social &
Environmental
Impact**




Recovery is Possible





Turning Pollution into an Asset





True Pigments – a Social Enterprise of Rural Action



Social enterprises operate based on four Ps:

1 Planet

2 People


3 Prosperity


4 Purpose




Social Return on Investment (SROI)

- SROI is a way of measuring the social, environmental, and economic impacts of a project that speaks the language of investors
- Each year of operations generates an SROI of \$15.97 for every \$1 invested
- Total economic impact of first year operations, including direct, indirect, induced effects, and taxes is \$2,178,309






Community Open Space



ALONG SUNDAY CREEK




UPPER WETLAND OBSERVATION AREA



ACCESS ROAD




LOWER WETLAND OBSERVATION AREA



WETLAND DIVERSION BERM



DIKE BERM AT SLUDGE POND






Pigment Production

- Sludge Production
- Dewatering
- Drying
- Grinding
- Kilning
- Quality Control
- Challenges



Dewatering with the Plate Press at Truetown







Dewatering and Drying










Grinding with the Ball Mill





Grinding with the Ball Mill





Firing Dried Pigment to Red and Violet









2025 Low pH AMD iron




Gamblin Raw iron



LOW PH
IRON
CALCINED




LOW PH IRON
CALCINED
1,000C



Challenges in Scaling Pigment Production


- Changes in the water treatment process directly affect pigment quality and characteristics
- Selection of equipment and process design must balance performance with long-term cost efficiency
- Solids handling, dewatering and drying, remains a key operational and design challenge
- Lack of onsite natural gas
- Market development is essential, as full-scale pigment production is still several years away




Reclaimed Earth Colors Oil Paints

Partnership with Gamblin Artists Colors

- Portland, Oregon
- Sold in art retailers worldwide
- Three colors all sourced from AMD pigments
- Interest in Iron Violet joining regular retail line






Iron Oxide Pigment Market

End uses for iron oxide pigments include:

- Artist paint
- Multi-use paint
- Industrial coatings
- Bricks
- Colored concrete products
- Tile
- Cosmetics including make-up and nail polish
- Fertilizer additive
- Arsenic removal for drinking water treatment
- pigment wholesalers and more




Education and Community Outreach



- Over 100 people have toured the Truetown site each year since Rural Action purchased property
- Ohio University and Hocking College classes are frequent visitors
- Coal India delegation visited in 2024







Phase I Construction Groundbreaking – June 2023




Groundbreaking brought 90+ folks to the site for the celebration



Films and National Media




Toxic Art
















Lithologic Detail













Q&A